

CITY OF MESA
MESA, ARIZONA

1ST STREET IMPROVEMENTS, COUNTRY CLUB DRIVE TO DATE STREET

PROJECT NO. 01-656-006

TABULATION OF BIDS RECEIVED ON THURSDAY, MARCH 19, 2009 @ 2:30 P.M.

ITEM NO.	DESCRIPTION	QUANTITY	ENGINEER'S ESTIMATE		SAHUARO PIPELINE CORP INC.		STANDARD CONSTRUCTION COMPANY INC.		VISUS ENGINEERING CONSTRUCTION	
			UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE
1	FURNISH AND INSTALL 8-INCH SEWER LINE	1,060 LF	50.00	53,000.00	63.29	67,087.40	33.00	34,980.00	40.00	42,400.00
2	FURNISH AND INSTALL 4-INCH SEWER SERVICE PER MAG STD DETAIL 440-1, CONNECT NEW SERVICE TO EXISTING PRIVATE SERVICE AT ROW LIMITS PER DETAIL 6 ON SHEET 7 OF THE APPROVED PLANS	850 LF	40.00	34,000.00	31.00	26,350.00	28.00	23,800.00	65.00	55,250.00
3	FURNISH AND INSTALL 5 FOOT DIAMETER MANHOLE WITH 30 INCH FRAME AND COVER PER MAG STD DETAIL 420-1, 420-2 AND 424. NO STEPS TO BE INSTALLED IN MANHOLE.	3 EA	2,500.00	7,500.00	2,150.00	6,450.00	4,600.00	13,800.00	2,000.00	6,000.00
4	FURNISH AND INSTALL SURVEY MONUMENT PER MAG STD DETAIL 120-1 TYPE A	2 EA	400.00	800.00	180.00	360.00	350.00	700.00	500.00	1,000.00
5	FURNISH AND INSTALL SANITARY SEWER CLEAN OUT PER MAG STD DETAIL 441. ADJUST FRAME AND COVER PER MAG STD DETAIL 270	1 EA	1,500.00	1,500.00	325.00	325.00	850.00	850.00	800.00	800.00
6	SAWCUT, REMOVE AND REPLACE PAVEMENT PER DETAIL 2, SHEET 6 OF THE APPROVED PLANS	725 SY	30.00	21,750.00	17.00	12,325.00	24.00	17,400.00	25.00	18,125.00
7	SAWCUT, REMOVE AND REPLACE PAVEMENT PER CITY OF MESA STD DETAIL M-19.4 TYPE B	10 SY	80.00	800.00	37.50	375.00	130.00	1,300.00	275.00	2,750.00
8	SAWCUT, REMOVE AND REPLACE SIDEWALK TO NEAREST JOINT PER MAG STD DETAIL 230	1,600 SF	12.00	19,200.00	6.65	10,640.00	9.00	14,400.00	2.50	4,000.00
9	REMOVE AND REPLACE COMPLETE SPEED HUMP PER COM STD DETAIL M-15.1 AND M-15.2	2 EA	4,000.00	8,000.00	2,420.00	4,840.00	500.00	1,000.00	2,900.00	5,800.00

CITY OF MESA
MESA, ARIZONA

1ST STREET IMPROVEMENTS, COUNTRY CLUB DRIVE TO DATE STREET

PROJECT NO. 01-656-006

TABULATION OF BIDS RECEIVED ON THURSDAY, MARCH 19, 2009 @ 2:30 P.M.

ITEM NO.	DESCRIPTION	QUANTITY	ENGINEER'S ESTIMATE		SAHUARO PIPELINE CORP INC.		STANDARD CONSTRUCTION COMPANY INC.		VISUS ENGINEERING CONSTRUCTION	
			UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE
10	REMOVE EXISTING SEWER MANHOLE CONE, PLUG SEWER LINE AND FILL REMAINING MANHOLE WITH ABC SLURRY	3 EA	1,500.00	4,500.00	600.00	1,800.00	1,300.00	3,900.00	1,000.00	3,000.00
11	FURNISH AND INSTALL 4-INCH DIP WATERLINE	5 LF	200.00	1,000.00	168.50	842.50	145.00	725.00	220.00	1,100.00
12	FURNISH AND INSTALL 6-INCH DIP WATERLINE	65 LF	150.00	9,750.00	33.80	2,197.00	37.00	2,405.00	70.00	4,550.00
13	FURNISH AND INSTALL 8-INCH DIP WATERLINE	1,250 LF	50.00	62,500.00	39.00	48,750.00	38.00	47,500.00	40.00	50,000.00
14	FURNISH AND INSTALL 8-INCH GATE VALVE, BOX AND COVER PER MAG STD DETAIL 391-1-C	4 EA	1,750.00	7,000.00	1,300.00	5,200.00	1,300.00	5,200.00	1,250.00	5,000.00
15	FURNISH AND INSTALL FIRE HYDRANT PER MAG 360 AND 6-INCH GATE VALVE PER MAG STD DETAIL 391-1-C	2 EA	3,000.00	6,000.00	3,250.00	6,500.00	3,300.00	6,600.00	3,200.00	6,400.00
16	FURNISH AND INSTALL COPPER WATER SERVICE 3/4-INCH PER COM STD DETAIL M-49.1 AND 49.2	750 LF	30.00	22,500.00	22.00	16,500.00	25.00	18,750.00	40.00	30,000.00
17	FURNISH AND INSTALL NEW WATER METER BOX AND COVER 3/4-INCH PER COM STD DETAIL M-49.1 AND 49.2	35 EA	55.00	1,925.00	66.00	2,310.00	140.00	4,900.00	90.00	3,150.00
18	SAWCUT, REMOVE AND SALVAGE EXISTING FIRE HYDRANT	2 EA	750.00	1,500.00	350.00	700.00	450.00	900.00	900.00	1,800.00
19	FURNISH AND INSTALL NEW 3/4-INCH SCHEDULE 40 PVC WATERLINE FROM NEW WATER METER BOX TO EXISTING PRIVATE SERVICE - CONNECT TO EXISTING SERVICE (18-INCH COPPER "PIG TAIL" REQUIRED PER COM STD DETAIL M-49.2)	35 EA	50.00	1,750.00	80.00	2,800.00	175.00	6,125.00	160.00	5,600.00

CITY OF MESA
MESA, ARIZONA

1ST STREET IMPROVEMENTS, COUNTRY CLUB DRIVE TO DATE STREET

PROJECT NO. 01-656-006

TABULATION OF BIDS RECEIVED ON THURSDAY, MARCH 19, 2009 @ 2:30 P.M.

ITEM NO.	DESCRIPTION	QUANTITY	ENGINEER'S ESTIMATE		SAHUARO PIPELINE CORP INC.		STANDARD CONSTRUCTION COMPANY INC.		VISUS ENGINEERING CONSTRUCTION	
			UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE
20	REMOVE AND DISPOSE OF EXISTING WATER METER BOX	35 EA	25.00	875.00	50.00	1,750.00	50.00	1,750.00	20.00	700.00
21	SAWCUT, REMOVE AND REPLACE EXISTING SIDEWALK RAMP PER DETAIL 4 SHEET 7 OF THE APPROVED PLANS.	4 EA	1,500.00	6,000.00	1,050.00	4,200.00	2,100.00	8,400.00	1,500.00	6,000.00
22	SAWCUT AND REMOVE EXISTING SIDEWALK RAMP, SIDEWALK, CURB AND GUTTER. INSTALL NEW RAMP PER COM STD DTL M-44.5 MODIFIED FOR 4-INCH ROLL CURB AND 4-FOOT DETACHMENT OF THE APPROVED PLANS AND REPLACE 12 LF OF CURB AND GUTTER PER MAG STD DETAIL 220 TYPE C	1 EA	3,000.00	3,000.00	1,050.00	1,050.00	3,400.00	3,400.00	1,800.00	1,800.00
23	ABANDON EXISTING VALVE PER DETAIL 1 SHEET 6 OF THE APPROVED PLANS	2 EA	100.00	200.00	75.00	150.00	120.00	240.00	200.00	400.00
24	MILL EXISTING AC PAVEMENT PER DETAIL 3 SHEET 6 OF THE APPROVED PLANS	1,850 SY	12.00	22,200.00	6.60	12,210.00	6.00	11,100.00	3.00	5,550.00
25	FURNISH AND INSTALL 1.5-INCH AC SURFACE COURSE OVERLAY R-12.5 PER DETAIL 3 SHEET 6 OF THE APPROVED PLANS	4,300 SY	20.00	86,000.00	8.00	34,400.00	7.00	30,100.00	6.00	25,800.00
26	FURNISH AND INSTALL 6-FOOT BY 60-FOOT QUADRAPOLE LOOP DETECTOR PER COM STD DETAIL 96.1, 96.2 AND 96.3	1 EA	1,500.00	1,500.00	2,500.00	2,500.00	1,800.00	1,800.00	1,000.00	1,000.00
27	SAWCUT, REMOVE AND REPLACE VALLEY GUTTER AND APRON TO NEAREST JOINT PER MAG STD DETAIL 240	300 SF	20.00	6,000.00	8.00	2,400.00	19.00	5,700.00	10.00	3,000.00

CITY OF MESA
MESA, ARIZONA

1ST STREET IMPROVEMENTS, COUNTRY CLUB DRIVE TO DATE STREET

PROJECT NO. 01-656-006

TABULATION OF BIDS RECEIVED ON THURSDAY, MARCH 19, 2009 @ 2:30 P.M.

ITEM NO.	DESCRIPTION	QUANTITY	ENGINEER'S ESTIMATE		SAHUARO PIPELINE CORP INC.		STANDARD CONSTRUCTION COMPANY INC.		VISUS ENGINEERING CONSTRUCTION	
			UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE
28	SAWCUT, REMOVE AND REPLACE EXISTING SIDEWALK RAMP PER COM STD DTL M-44.2 (TURNATED DOMES TO BE YELLOW TO MATCH EXISTING).	1 EA	3,500.00	3,500.00	1,050.00	1,050.00	2,300.00	2,300.00	1,500.00	1,500.00
29	ADVANCED WARNING SIGN ALLOWANCE	LUMP SUM	LUMP SUM	1,500.00	LUMP SUM	1,500.00	LUMP SUM	1,500.00	LUMP SUM	1,500.00
30	RESTORE EXISTING PRIVATE LANDSCAPING	LUMP SUM	LUMP SUM	5,000.00	LUMP SUM	2,750.00	LUMP SUM	11,000.00	LUMP SUM	3,200.00
31	CONSTRUCTION SURVEY	LUMP SUM	LUMP SUM	3,000.00	LUMP SUM	4,257.00	LUMP SUM	4,500.00	LUMP SUM	2,900.00
32	QUALITY CONTROL TESTING PROGRAM	LUMP SUM	LUMP SUM	7,650.00	LUMP SUM	5,500.00	LUMP SUM	6,000.00	LUMP SUM	5,000.00
33	ALLOWANCE FOR PERMIT FEES	LUMP SUM	LUMP SUM	1,000.00	LUMP SUM	1,000.00	LUMP SUM	1,000.00	LUMP SUM	1,000.00
	<u>CONTINGENCY ITEMS</u>									
34	SAWCUT, REMOVE AND REPLACE CURB AND GUTTER PER MAG STD DETAIL 220 TYPE C	300 LF	20.00	6,000.00	16.00	4,800.00	30.00	9,000.00	11.00	3,300.00
35	SAWCUT, REMOVE AND REPLACE SIDEWALK PER MAG STD DETAIL 230	800 SF	12.00	9,600.00	6.65	5,320.00	7.00	5,600.00	3.00	2,400.00
36	REMOVE EXISTING PRIVATE SEWER SERVICES. FURNISH AND INSTALL 4-INCH PVC PRIVATE SEWER SERVICE CONNECT TO EXISTING PRIVATE SERVICE	300 LF	40.00	12,000.00	11.50	3,450.00	20.00	6,000.00	12.00	3,600.00
TOTAL BASE BID (Items 1 through 36)				440,000.00		304,638.90		314,625.00		315,375.00

ADDITIONAL BIDDERS

KELCO LLC

327,960.00

