

CITY OF MESA
MESA, ARIZONA

ELECTRIC CIRCUIT CONVERSION - CIRCUIT 101 UNDERGROUND

PROJECT NO. 02-384-004

TABULATION OF BIDS RECEIVED ON THURSDAY, JUNE 11, 2009, AT 1:00 P.M.

ITEM NO.	DESCRIPTION	QUANTITY	ENGINEER'S ESTIMATE		UTILITY CONSTRUCTION CO INC.		PAULEY CONSTRUCTION INC.		UNDERGROUND UTILITIES INC.	
			UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE
1.	Furnish and install 2 each 4-inch electrical conduits by horizontal directional bore (a 9-inch bore is anticipated). Include all elbows and sweeps shown on the drawings and in the specifications. Furnish and install plugs and caps to protect conduit installation.	2,593 LF	32.69	84,765.17	22.75	58,990.75	24.50	63,528.50	28.29	73,355.97
2.	Install electrical switching cabinet with ground sleeve and ground rod as shown on drawing details. City will provide the cabinet and ground sleeve. Contractor shall provide ground rod.	3 EA	500.00	1,500.00	500.00	1,500.00	1,500.00	4,500.00	1,302.98	3,908.94
3.	Furnish and install 1 each 10-foot length of 4-inch rigid galvanized steel conduit and 2 each conduit standoff brackets on a wood pole using lag screws as shown on drawing detail.	1 EA	425.00	425.00	400.00	400.00	75.00	75.00	556.83	556.83
4.	Furnish City with 2 each 10-foot lengths of 4-inch rigid galvanized steel conduit, 4 each conduit standoff brackets and lag screws for City to complete the riser installation.	1 EA	425.00	425.00	250.00	250.00	100.00	100.00	913.20	913.20
5.	Furnish and install 1 each 10-foot length of 4-inch rigid galvanized steel conduit and 2 each conduit standoff brackets on a steel pole stainless steel banding and banding hardware as shown on drawing detail.	1 EA	525.00	525.00	420.00	420.00	125.00	125.00	612.51	612.51

**CITY OF MESA
MESA, ARIZONA**

ELECTRIC CIRCUIT CONVERSION - CIRCUIT 101 UNDERGROUND

PROJECT NO. 02-384-004

TABULATION OF BIDS RECEIVED ON THURSDAY, JUNE 11, 2009, AT 1:00 P.M.

ITEM NO.	DESCRIPTION	QUANTITY	ENGINEER'S ESTIMATE		UTILITY CONSTRUCTION CO INC.		PAULEY CONSTRUCTION INC.		UNDERGROUND UTILITIES INC.	
			UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE
6.	Furnish City with 2 each 10-foot lengths of 4-inch rigid galvanized steel conduit, 4 each conduit standoff brackets and stainless steel banding and banding hardware for City to complete the riser installation.	1 EA	525.00	525.00	270.00	270.00	100.00	100.00	1,057.98	1,057.98
7.	Furnish and install 3 each #2 AWG, 15kV URD cable into one of the installed 4-inch conduits. Seal all cable ends. City will provide materials and terminate cables.	2,773 LF	6.75	18,717.75	10.00	27,730.00	10.35	28,700.55	7.35	20,381.55
8.	Sawcut, remove and replace sidewalk per MAG Std Detail 230.	32 SF	15.00	480.00	10.00	320.00	18.00	576.00	11.14	356.48
9.	Sawcut, remove and replace pavement per COM Std Detail M-19.4, Type B.	144 SF	10.00	1,440.00	10.00	1,440.00	15.00	2,160.00	13.36	1,923.84
10.	Restore existing private alley surfacing dirt	LUMP SUM	LUMP SUM	1,000.00	LUMP SUM	500.00	LUMP SUM	1,880.00	LUMP SUM	750.00
11.	Allowance for permit fees	LUMP SUM	LUMP SUM	1,000.00	LUMP SUM	1,000.00	LUMP SUM	1,000.00	LUMP SUM	1,000.00
12.	Off-Duty Mesa Police Officer (Contingency Bid Item)	100 HRS	50.00	5,000.00	40.00	4,000.00	60.00	6,000.00	50.11	5,011.00
13.	Advanced warning sign allowance	LUMP SUM	LUMP SUM	2,000.00	LUMP SUM	2,000.00	LUMP SUM	2,000.00	LUMP SUM	2,000.00
14.	Remove 1 each wood pole and framing	2 EA	450.00	900.00	200.00	400.00	250.00	500.00	334.10	668.20
15.	Remove 1 each down guy and cut off 1 each anchor 6-inch below grade	2 EA	300.00	600.00	150.00	300.00	150.00	300.00	111.37	222.74

CITY OF MESA
MESA, ARIZONA

ELECTRIC CIRCUIT CONVERSION - CIRCUIT 101 UNDERGROUND

PROJECT NO. 02-384-004

TABULATION OF BIDS RECEIVED ON THURSDAY, JUNE 11, 2009, AT 1:00 P.M.

ITEM NO.	DESCRIPTION	QUANTITY	ENGINEER'S ESTIMATE		UTILITY CONSTRUCTION CO INC.		PAULEY CONSTRUCTION INC.		UNDERGROUND UTILITIES INC.		
			UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	
16.	Remove and scrap 4 each overhead conductors (3 phases plus neutral), insulators and associated hardware from poles and cross arms as identified on Approved Demolition Plans	562 LF	0.35	196.70	3.00	1,686.00	4.45	2,500.90	1.67	938.54	
17.	Remove and scrap 3 each overhead conductors, insulators and associated hardware from crossarms as identified on Approved Demolition Plan	1,838 LF	0.32	588.16	2.00	3,676.00	4.45	8,179.10	1.67	3,069.46	
18.	Repair/replace private irrigation pipes that are damaged during construction (Contingency Bid Item)	300 LF	40.00	12,000.00	5.00	1,500.00	10.00	3,000.00	44.55	13,365.00	
TOTAL BASE BID (Items 1 through 18)					132,087.78		106,382.75		125,225.05		130,092.24

ADDITIONAL BIDDERS

STURGEON ELECTRIC COMPANY INC.	133,220.15
KIMBRELL ELECTRIC INC.	136,561.57
KLEVEN CONSTRUCTION	137,514.00
PARAMOUNT DESIGNS INC. DBA PDI CONSTRUCTION	138,732.09
THE FISHEL COMPANY	152,105.33
NPL CONSTRUCTION COMPANY	160,414.28
COMMONWEALTH ELECTRIC COMPANY OF THE MIDWEST	192,147.75
RURAL ELECTRIC INC.	200,000.00