

CITY OF MESA
MESA, ARIZONA

DESERT WELL NO. 21 EQUIPPING, 11010 EAST ELLIOT ROAD

PROJECT NO. 05-065-002

TABULATION OF BIDS RECEIVED THURSDAY, DECEMBER 17, 2009, AT 1:00 P.M.

ITEM NO.	DESCRIPTION	QUANTITY	ENGINEER'S ESTIMATE		WEBER GROUP LC		PRIME CONTRACTING LLC		HAYDON BUILDING CORP.	
			UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE
1.	Furnish and install new turbine pump bowl, motor, discharge head, 12-inch and 8-inch DIP (PC 350) aboveground water line, fittings, meters, check valves, gate valves, pump control valve, DIP piping supports and all appurtenances	LUMP SUM	LUMP SUM	175,000.00	LUMP SUM	146,218.00	LUMP SUM	182,279.00	LUMP SUM	190,000.00
2.	Furnish and install new 12-inch diameter column pipe assembly with 3/8-inch brass air line	700 LF	150.00	105,000.00	73.75	51,625.00	77.00	53,900.00	140.00	98,000.00
3.	Furnish and install new 12-inch DIP (PC 350) underground waterline, including pipe inside and outside the well site)	123 LF	110.00	13,530.00	84.00	10,332.00	140.00	17,220.00	78.00	9,594.00
4.	Install sampling station complete per details on the Approved Plans and per the Technical Provisions (includes rip rap for erosion control)									
	NOTE: The City of Mesa will provide the sampling station riser and housing and the Contractor shall install this equipment. The Contractor shall be responsible for furnishing all other equipment necessary and for installation of said equipment per the details on the Approved Plans and per the Technical Provisions.	1 EA	2,400.00	2,400.00	2,215.00	2,215.00	3,396.00	3,396.00	645.00	645.00
5.	Furnish and install new 18-inch RGRCP (Class III) drain line	14 LF	250.00	3,500.00	326.00	4,564.00	62.00	868.00	120.00	1,680.00
6.	Furnish and install 30-inch diameter standpipe system including metal enclosure	1 EA	7,000.00	7,000.00	2,642.00	2,642.00	6,448.00	6,448.00	1,485.00	1,485.00

CITY OF MESA
MESA, ARIZONA

DESERT WELL NO. 21 EQUIPPING, 11010 EAST ELLIOT ROAD

PROJECT NO. 05-065-002

TABULATION OF BIDS RECEIVED THURSDAY, DECEMBER 17, 2009, AT 1:00 P.M.

ITEM NO.	DESCRIPTION	QUANTITY	ENGINEER'S ESTIMATE		WEBER GROUP LC		PRIME CONTRACTING LLC		HAYDON BUILDING CORP.	
			UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE
7.	Furnish and install new chlorine system including chlorinator, pump, ejector assembly, corporation cock/diffuser assembly, piping, PVC piping supports, valves, pressure gauges and other chlorine system appurtenances	LUMP SUM	LUMP SUM	30,000.00	LUMP SUM	39,702.00	LUMP SUM	42,184.00	LUMP SUM	36,000.00
8.	Furnish and install new chlorine enclosure with warning signs and all appurtenances	LUMP SUM	LUMP SUM	20,000.00	LUMP SUM	14,400.00	LUMP SUM	18,722.00	LUMP SUM	18,000.00
9.	Furnish and install new acoustical enclosure per the Approved Plans and Specifications	LUMP SUM	LUMP SUM	20,000.00	LUMP SUM	27,228.00	LUMP SUM	20,061.00	LUMP SUM	29,000.00
10.	Furnish and install electrical layout (excluding work covered by Bid Items 11 through 14), new service entrance section/motor control center, electric meter, cabinet, all conduit within well site that is on the customer's side of the electric meter, wiring and terminations, all associated conduit trenching, backfill and compaction, and all other items necessary to complete the electrical portion of this project per the Approved Plans and Specifications	LUMP SUM	LUMP SUM	160,000.00	LUMP SUM	210,007.00	LUMP SUM	185,673.00	LUMP SUM	224,500.00
11.	Furnish and install three (3) 3-inch PVC conduits, including trenching, backfill, compaction stub-ups pull tape, caps and plugs per the Approved Plans and Specifications and SRP requirements	410 LF	19.00	7,790.00	13.00	5,330.00	14.00	5,740.00	14.00	5,740.00
12.	Bore three (3) 3-inch PVC conduits from existing SRP manhole #0303 to north side of Elliot Road per the Approved Plans and Specifications and SRP requirements. Includes conduit and pull tape	105 LF	35.00	3,675.00	81.00	8,505.00	85.00	8,925.00	28.00	2,940.00

**CITY OF MESA
MESA, ARIZONA**

DESERT WELL NO. 21 EQUIPPING, 11010 EAST ELLIOT ROAD

PROJECT NO. 05-065-002

TABULATION OF BIDS RECEIVED THURSDAY, DECEMBER 17, 2009, AT 1:00 P.M.

ITEM NO.	DESCRIPTION	QUANTITY	ENGINEER'S ESTIMATE		WEBER GROUP LC		PRIME CONTRACTING LLC		HAYDON BUILDING CORP.	
			UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE
13.	Furnish and install precast concrete pad for SRP switch per the Approved Plans and Specifications and SRP requirements	1 EA	3,000.00	3,000.00	1,662.00	1,662.00	1,281.00	1,281.00	840.00	840.00
14.	Furnish and install precast concrete pad for SRP transformer per the Approved Plans and Specifications and SRP requirements	1 EA	3,000.00	3,000.00	3,323.00	3,323.00	1,169.00	1,169.00	1,400.00	1,400.00
15.	Furnish and install new well site sign and N.F.P.A. Hazardous Materials identification sign on 25-foot wide gate per the Approved Plans	LUMP SUM	LUMP SUM	1,000.00	LUMP SUM	875.00	LUMP SUM	601.00	LUMP SUM	345.00
16.	Furnish and install new oil drum (filled with white mineral oil per the Technical Specifications), stand, piping, and warning signs	LUMP SUM	LUMP SUM	2,000.00	LUMP SUM	1,329.00	LUMP SUM	1,192.00	LUMP SUM	480.00
17.	Furnish and install concrete pump pad complete	LUMP SUM	LUMP SUM	10,000.00	LUMP SUM	5,273.00	LUMP SUM	6,413.00	LUMP SUM	1,300.00
18.	Furnish and install 6-inch thick, reinforced concrete pads (includes pad for SES)	136 SF	25.00	3,400.00	14.00	1,904.00	12.00	1,632.00	5.50	748.00
19.	Furnish and install 8-inch thick unreinforced concrete pads	14 SF	40.00	560.00	32.00	448.00	9.00	126.00	5.00	70.00
20.	Furnish and install 10-inch thick reinforced concrete pad for chlorine enclosure	54 SF	50.00	2,700.00	16.50	891.00	11.00	594.00	13.00	702.00
21.	Furnish and install 6-inch thick, reinforced concrete pad with perimeter curb for secondary containment of pump lubricating oil	LUMP SUM	LUMP SUM	1,000.00	LUMP SUM	775.00	LUMP SUM	1,292.00	LUMP SUM	700.00

**CITY OF MESA
MESA, ARIZONA**

DESERT WELL NO. 21 EQUIPPING, 11010 EAST ELLIOT ROAD

PROJECT NO. 05-065-002

TABULATION OF BIDS RECEIVED THURSDAY, DECEMBER 17, 2009, AT 1:00 P.M.

ITEM NO.	DESCRIPTION	QUANTITY	ENGINEER'S ESTIMATE		WEBER GROUP LC		PRIME CONTRACTING LLC		HAYDON BUILDING CORP.	
			UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE
22.	Furnish and install 2-inch thick (compacted depth) decomposed granite (3/8-inch minus) with pre-emergent herbicide	1,200 SY	4.00	4,800.00	4.00	4,800.00	7.00	8,400.00	4.75	5,700.00
23.	Furnish and install 2-inch thick (compacted depth) decomposed granite (1/4-inch minus) with "Marloc-ss" on retention basin side slopes and in swale	1,100 SY	5.00	5,500.00	5.00	5,500.00	7.00	7,700.00	7.15	7,865.00
24.	Perform all clearing, grubbing and grading operations within well site boundary and setback areas required to achieve finished grades noted on Approved Plans (includes removal and disposal of existing trees or shrubs)	LUMP SUM	LUMP SUM	20,000.00	LUMP SUM	16,627.00	LUMP SUM	22,034.00	LUMP SUM	2,500.00
25.	Construction survey and staking	LUMP SUM	LUMP SUM	5,000.00	LUMP SUM	5,539.00	LUMP SUM	6,898.00	LUMP SUM	3,000.00
26.	Furnish and install new vertical underground drain per Detail "A" on Sheet No. 11 of the Approved Plans including 3-inch diameter polyethylene grate and 3-inch PVC underground connection to drain	1 EA	1,500.00	1,500.00	1,052.00	1,052.00	1,487.00	1,487.00	860.00	860.00
27.	Construct low CMU wall with ornamental steel fence and steel security top and CMU pilasters per the Approved Plans and Specifications	471 LF	160.00	75,360.00	83.00	39,093.00	160.00	75,360.00	88.00	41,448.00
28.	Furnish and install new 25-foot wide roll gate with steel security top	1 EA	10,000.00	10,000.00	3,988.00	3,988.00	4,463.00	4,463.00	4,300.00	4,300.00
29.	Furnish and install 4-foot wide man gate with steel security top	1 EA	2,500.00	2,500.00	526.00	526.00	194.00	194.00	575.00	575.00

**CITY OF MESA
MESA, ARIZONA**

DESERT WELL NO. 21 EQUIPPING, 11010 EAST ELLIOT ROAD

PROJECT NO. 05-065-002

TABULATION OF BIDS RECEIVED THURSDAY, DECEMBER 17, 2009, AT 1:00 P.M.

ITEM NO.	DESCRIPTION	QUANTITY	ENGINEER'S ESTIMATE		WEBER GROUP LC		PRIME CONTRACTING LLC		HAYDON BUILDING CORP.	
			UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE	UNIT PRICE	TOTAL PRICE
30.	Furnish spare signs for the site per Section 13 of the Technical Specifications	LUMP SUM	LUMP SUM	2,500.00	LUMP SUM	2,570.00	LUMP SUM	1,114.00	LUMP SUM	700.00
31.	Furnish and install rip rap erosion protection in on-site retention basin, per the Approved Plans	LUMP SUM	LUMP SUM	5,000.00	LUMP SUM	5,649.00	LUMP SUM	2,627.00	LUMP SUM	2,600.00
32.	Furnish and install drywell per the Approved Plans	2 EA	6,000.00	12,000.00	7,200.00	14,400.00	8,218.00	16,436.00	8,900.00	17,800.00
33.	Additional drywell depth beyond the estimated 120-foot depth shown on the Approved Plans (Contingency bid item)	100 VF	15.00	1,500.00	72.00	7,200.00	37.00	3,700.00	50.75	5,075.00
34.	Furnish and install 8" thick ABC access drive per the Approved Plans	200 SY	20.00	4,000.00	8.25	1,650.00	15.00	3,000.00	8.55	1,710.00
35.	Furnish and install concrete retainer curb for the access drive per the Approved Plans	153 LF	10.00	1,530.00	10.00	1,530.00	27.00	4,131.00	5.00	765.00
36.	Removal and disposal of Asbestos Cement Pipe (Contingency bid item)	100 LF	50.00	5,000.00	11.00	1,100.00	8.00	800.00	8.50	850.00
37.	Allowance for permit fees	LUMP SUM	LUMP SUM	1,000.00	LUMP SUM	1,000.00	LUMP SUM	1,000.00	LUMP SUM	1,000.00
TOTAL BASE BID (Items 1 through 37)				731,745.00		651,472.00		719,060.00		720,917.00

ADDITIONAL BIDDERS

CITY WIDE CONTRACTING LLC	752,515.00
FELIX CONSTRUCTION COMPANY	761,789.00
GILBERT PUMP AND EQUIPMENT CO.	784,756.00
CURRIER CONSTRUCTION INC.	836,432.00
NORQUAY CONSTRUCTION INC.	873,254.84
RK SANDERS INC.	BID NOT READ - DID NOT USE CORRECT BID SCHEDULE
SPIRE ENGINEERING LLC	BID REJECTED - INSUFFICIENT BOND RATING